


Harry Kim
Mayor



Christopher J. Yuen
Director

Brad Kurokawa, ASLA
LEED® AP
Deputy Director

County of Hawaii
PLANNING DEPARTMENT

101 Pauahi Street, Suite 3 • Hilo, Hawaii 96720-4224
(808) 961-8288 • FAX (808) 961-8742

December 7, 2007

Mr. Carl N. Nakayama
and Mrs. Shyran K. Nakayama
148 Mikihala Street
Hilo, Hawai'i 96720

Dear Mr. and Mrs. Nakayama:

Ohana Dwelling Unit Permit Application (OHD-07-000105)
Applicant(s): Carl N. Nakayama and Shyran K. Nakayama
Land Owner(s): Carl N. Nakayama and Shyran K. Nakayama
Proposal: Construct A Detached Ohana Dwelling Unit
Tax Map Key: (3) 2-4-010:124

The subject Application for an Ohana Dwelling Unit Permit was reviewed by the required agencies and their respective comments are as follows:

1. The Department of Public Works (DPW):

The DPW did not comment on this application as of this date.

2. The Department of Water Supply (DWS) (memorandum dated October 20, 2007):

"We have reviewed the subject application and have the following comments and conditions.

Please be informed that the subject parcel is currently served by a 5/8-inch meter, which is adequate for only one dwelling at an average daily usage of 400 gallons. Inasmuch as this application is proposing an additional dwelling, the installation of a separate 5/8-inch meter will be required. Water can be made available from the Department's existing 6-inch waterline within Mikihala Street, fronting the subject parcel.

Therefore, the Department has no objections to the proposed application, subject to the applicant understanding and accepting the following conditions:

1. Installation, by the Department of Water Supply, of a 1-inch service lateral to service a 5/8-inch meter, which shall be restricted to a maximum daily-flow of 600 gallons.
2. Remittance of the following charges, which are subject to change, to our Customer Service Section:

FACILITIES CHARGE (FC):	
2 nd service to the parcel	\$5,500.00
SERVICE LATERAL INSTALLATION CHARGE:	
<u>Install one meter on Mikihala Street, a County road</u>	<u>\$2,600.00</u>
Total (Subject to Change)	\$8,100.00

Should there be any questions, please contact Mr. Ryan Quitoriano of our Water Resources and Planning Branch at 961-8070, extension 256.”

3. The State of Hawaii Department of Health (DOH-HILO) (memorandum dated October 22, 2007):

“Wastewater Branch is unable to make comments to the proposed project at this time. Before we can offer any comments, the applicant needs to address the location of all existing wastewater systems.

Portion of the subdivision is located within 1,000 ft. of a public water source. You are required to show the 1,000 ft. radius from the water source on the site plan. No cesspool can be installed within this 1,000 ft. radius. Within the 1,000 ft. radius, an aerobic treatment unit system may be required for sewage treatment.

We recommend that you review all of the Standard Comments on our website: www.state.hi.us/health/environmental/env-planning/landuse/landuse.html. Any comments specifically applicable to this project should be adhered to.”

4. The Hawaii County Fire Department (HFD) (memorandum dated November 6, 2007):

“We have no comments to offer at this time in reference to the above-mentioned Ohana dwelling permit application.”

Mr. Carl N. Nakayama
and Mrs. Shyran K. Nakayama
Page 3
December 7, 2007

We note the following document that accompanied your application. The original and notarized affidavit of **Carl and Shyran Nakayama**, dated September 11, 2007, included with the Ohana Dwelling application states:

“We, Carl and Shyran Nakayama, are the title holders of the property located at 148 Mikihala Street, Hilo, Hawaii 96720, Tax Map Key 3-2-4-10-124.

There are no restrictions, covenants or other land use restrictions on this property by way of deed or lease or any other provision that prohibit the construction or placement of an Ohana dwelling unit on this property.”

In view of the above, by this letter, you are hereby **granted** permission to construct a detached single-family Ohana Dwelling Unit subject to the following conditions:

1. The proposed Ohana Dwelling Unit shall comply with Ordinance No. 96-47 and Rule 12, the County of Hawaii Planning Department's Rules of Practice and Procedure relating to Ohana Dwelling Units.
2. Non-transferability: The permit for the Ohana Dwelling Unit shall be personal to the applicant until construction of the Ohana Dwelling Unit has been completed. The permit shall not be transferable or assignable to any other person prior to its completion to the satisfaction of the Chief Engineer, Department of Public Works.
3. Prohibition of Advertising, Sales, Transfers: No person shall advertise or represent to the public that a permit to construct an Ohana Dwelling Unit is transferable with the sale of the property on which the permit has been granted.
4. Building Permit: **The applicant is required to secure a building permit from the Department of Public Works, Building Division, for the construction of the Ohana Dwelling Unit on or before December 8, 2008.**

Please bring or attach a copy of this Permit to assist the reviewing agencies in understanding and expediting the review and processing of the building construction plans and building permit application for the additional building improvements necessary to establish the Ohana Dwelling on the subject parcel.

- a) A one time 30-day time extension to obtain the building permit may be granted by the Planning Director. A written request for a time extension shall be filed with the Planning Director not less than forty-five (45) days prior to the expiration date of the Ohana Dwelling Unit permit. The Planning Director shall render a decision on the request for a time extension prior to the expiration date of the permit.

- b) The applicant shall not be able to obtain further extensions beyond the initial 30-day time extension. Further, such failure to conform to the time requirement shall not be cause to petition the Planning Director, Board of Appeals or any other governmental body for relief from the time requirement.

5. Requirements for Height, Site Area (Lot size), Yard (Setback) and Off-Street Parking (Parking spaces):

- a) Height limit: The height limit for the proposed detached Ohana Dwelling Unit shall be twenty-five (25'-0") feet.
- b) Zoning and Minimum Building Site Area (Lot Size): The subject TMK parcel containing 19,687 sq.ft. is zoned Residential (RS-15) by the County and is situated within the State Land Use Urban district.
- c) Minimum Yards (Setbacks) and Open Space: The proposed Dwelling Unit is required to comply with the yards and open space requirements of the Hawaii County Zoning Code.

The respective minimum open space, front, rear, and side yard requirements for the proposed detached Ohana Dwelling Unit to be located on the subject TMK property shall be as follows:

- Front yard - minimum **twenty five** (25) feet required;
 - Rear yard – minimum **twenty five** (25) feet required;
 - Side yard(s) – minimum **fifteen** (15) feet required;
 - Open space from other main structure(s) – minimum **fifteen** (15) feet required.
- d) Off-Street Parking: The Ohana Dwelling Unit shall be provided with a minimum of two (2) off-street parking spaces that comply with the requirements of Section 25-4-53 of the Zoning Code. All existing and additional parking spaces shall be arranged so as to be individually accessible.

6. The DWS requires that an additional meter be installed for the Ohana Dwelling Unit. Prior to, or at the time of, submitting an application for a building permit for this dwelling, present proof of conformance with that condition. The building permit application will not be approved by the Planning Department without said proof.

Mr. Carl N. Nakayama
and Mrs. Shyran K. Nakayama
Page 5
December 7, 2007


7. This Ohana Dwelling permit is subject to all other applicable rules, regulations and requirements of the Planning Department, Department of Public Works, Fire Department and State Department of Health and other reviewing agencies/divisions listed on the Building Permit Application.
8. The Department of Health requires that you indicate on the building permit application site plan the 1,000 ft. radius of the nearest public water source. You may wish to consult with them and/or the Department of Water Supply for the location of that water source.

Ohana Dwelling Units are prohibited on a building site that is the subject of an approved variance from the Subdivision Code (Chapter 23), the Zoning Code Chapter 25), and property where a second Dwelling Unit is specifically prohibited by a change of zone ordinance.

- a) No variance from the requirements of Chapter 23 and Chapter 25, Hawaii County Code, as amended, shall be granted to permit the construction or placement of an Ohana Dwelling Unit.
- b) An Ohana Dwelling Unit shall not be permitted on a lot which has been the subject of a previously granted variance from any provision of Chapter 23 and Chapter 25, Hawaii County Code, as amended.

Should you have any questions regarding the above, please contact Jonathan Holmes of this office.

Sincerely,





CHRISTOPHER J. YUEN
Planning Director

JRH:cd

o:\ohana\jr\ohana\apvl\nakayama24010124apvl.doc

xc: Dept. of Health, Chief Sanitarian
Dept. of Public Works
Real Property Tax
Dept. of Water Supply




MIKIHALA

PLOT PLAN

1:20

TMK: 3-2-4-10:124
 ZONING: RS-15
 LOT AREA: 19661.31 sq ft



New Residence for M&M Nakayama 148 Mikihala St. Hilo, Hawaii TMK 3-2-4-10:124	Plot Plan A-1 of 9 March 5, 2007
---	---

THIS WORK WAS PREPARED BY ME OR UNDER MY SUPERVISION AND CONSTRUCTION OF THIS PROJECT WILL BE UNDER MY OBSERVATION.

[Handwritten Signature]

REV 4/30/07